

## ANALYSIS REPORT

Gypsum Supplies  
PO Box 18  
KALANNIE WA 6468

ATTENTION Daniel Nixon  
FAX NUMBER  
PURCHASE ORDER Received 9.1.18  
PROJECT NUMBER B1801-0100

DATE RECEIVED 09 January 2018  
OUR SAMPLE NUMBER B2018-00200  
YOUR REFERENCE 319N  
SAMPLE TYPE Gypsum  
SAMPLE DESCRIPTION Gypsum Sample

TEST	Result
<b>Analysis of Gypsum (FDA VGB-M701 2nd ed 2008)</b>	
Calcium (% W/W (dry wt))	21.4
Sulphate (% W/W (dry wt))	52.6
Gypsum - CaSO <sub>4</sub> x 2H <sub>2</sub> O (% W/W (dry wt))	92
Sulphur (% W/W (dry wt))	17.5
<b>Particle Size Distribution (na)</b>	
0 - 0.125 mm (% W/W)	2.4
0.125 - 0.250 mm (% W/W)	5.1
0.250 - 0.500 mm (% W/W)	17.5
0.500 - 1.00 mm (% W/W)	35.4
>1.00 mm (% W/W)	39.6

**Note:** All samples are analysed on an as received basis.

This report is not to be reproduced except in full.

TP refers to the technical procedure used to conduct the analysis.

If test method is prefaced by:

TP or FT	Analysis conducted at Agrifood Technology, Victoria: Werribee Site.
TP_WA	Analysis conducted at Agrifood Technology, Western Australia: Bibra Lake Site.
TP_DML	Analysis conducted at Agrifood Technology, Victoria: Derrimut Site.
OS	Analysis is outsourced.

### Final Report

Report Number: 217712



**Mario Horvat**  
Laboratory Controller, WA  
30 January 2018

Report Number: 217712

Issued: 30 Jan 2018

Page 1 of 1